

Conditions of Acceptability:

1. These units are provided with a R/C (OBJY2) Class 155(F) insulation system.
2. Leakage current measurements shall be performed on the combination at the equipment connection in the end-use product.
3. The primary input terminal block terminals are to be torqued to 3.5 lb-in and installed with 20 or 22 AWG conductors, acceptability of the connection is to be determined in the end-use product.
4. The primary input strain relief has not been evaluated and shall be evaluated in the end-use product.
5. The Normal Temperature Test was conducted in an ambient of 50C at 3.8A and 70C at 1.52A. The need to conduct the temperature test in the end-use product shall be determined in the end use.